



This project has received funding from the Fuel Cells and Hydrogen 2 Joint Undertaking (now Clean Hydrogen Partnership) under Grant Agreement No 875090. This Joint Undertaking receives support from the European Union's Horizon 2020 research and innovation programme, Hydrogen Europe and Hydrogen Europe Research.

THE ENGINE OF THE HOME OF THE FUTURE



Visit of Pacific Northwest region

October 23, 2025

Kees Boer, Municipality of Hoogeveen





This project has received funding from the Fuel Cells and Hydrogen 2 Joint Undertaking (now Clean Hydrogen Partnership) under Grant Agreement No 875090. This Joint Undertaking receives support from the European Union's Horizon 2020 research and innovation programme, Hydrogen Europe and Hydrogen Europe Research.



Het demonstratie-project is mede mogelijk gemaakt door ondersteuning vanuit de Rijksdienst voor Ondernemend Nederland (RVO), Project nr. TWA2018013 project 'WATERSTOFWIJK HOOGEVEEN', onderdeel Regeling nationale EZ-subsidies: §4.2.8 Pilots Waterstof.



MEER KLIMAAT

Inloggen

Registreren

Over PAW

Helpdesk

Zoeken



Home

Thema's

Nieuws

Proeftuinen

Kennis- en leerprogramma

Vraag en antwoord

Kalender

Community



European Regional Development Fund



EUROPEAN UNION

provincie
Drenthe

Regio Deal

Zuid- en Oost-Drenthe



Home > Proeftuinen > Proeftuin Erlanden

Proeftuin Erlanden

Dossier op
rijksoverheid.nl




GREEN HYDROGEN, THE ENGINE OF THE HOME OF THE FUTURE

Hoogeveen wants to show that green hydrogen can make an important contribution to make a part of the Dutch housing stock natural gas-free, with:

- reuse of the existing natural gas network
- a new hydrogen central heating boiler.

With this pilot we contribute to the knowledge in the Netherlands for the possible upscaling of hydrogen in the built environment after 2030.


CONSORTIUM WATERSTOFWIJK HOOGEVEEN



Hydrogen District Hoogeveen

1. Realizing the hydrogen network
2. Connecting 100 new-build homes in Nijstad-Oost
3. Conversion of 100 to 427 homes in the existing Erflanden district from natural gas to hydrogen, by reusing the existing natural gas network and replace the natural gas boilers with hydrogen boilers.

1. H2-unloading station
2. 4 bar net
3. Pressure reduction
4. 100 millibar net
5. Electrolyzer RWZI
6. Connection to the national H2 grid






Hydrogen distribution network



HYDROGEN VALLEY

WATERSTOFHOOGEVEEN



This project has received funding from the Fuel Cells and Hydrogen 2 Joint Undertaking under Clean Hydrogen Partnership under Grant agreement No. 1010190. The Joint Undertaking receives support from the European Union's Horizon 2020 research and innovation programme, Hydrogen Europe and Hydrogen Europe Research.



Expected activities in the home

- replace boiler
- replace gas meter
- pressure testing
- H2 sensors



Ruikt u gas, gaat een waterstofsensor af of heeft u geen gas, bel RENDO:

0800-9009

Vertel erbij dat u in een waterstofwoning woont

OVERIGE STORINGEN

aan de waterstof installatie
of CV-ketel, bel Van Dorp:

0528-279158

Vertel erbij dat u in een waterstofwoning woont



De waterstof cv-ketel

- 24/28kW CW4 100% waterstof cv-ketel (veldtest toestel)
- Vergevoerd stadium van ontwikkeling
- Geassembleerd op nieuw ontwikkelde productielijn met end of line test

Gelijkenissen aardgasketel

- Afmetingen
 - Gasvoordruk (20-30mbar)
 - Comfortsoftware
 - Prestaties en rendement
-
- Bruikleenovereenkomst
 - Twee jaar na plaatsingsdatum

Afwijkingen aardgasketel

- Ketel verzegeld
- Vlamterugslagbeveiliging ingebouwd
- H₂-lekdetectiesensor
- Extra veiligheidssoftware
- Geen CO₂ uitstoot



Waterstof in combinatie met warmtepomp



Hybride
warmtepomp



Up to 70% gas
reduction



Positioning



A solution that is safe, comfortable and affordable;

A solution that must be taken into account;

A solution that keeps options open;

A solution that creates space for gradualness;

A solution with opportunities after 2030?

Public support



Residents Council Hydrogen Erflanden

- Independent residents council
- Independent project leader employed by the residents



Involving the residents

- Working groups with professionals and residents
- Collecting feedback: what is important for the resident?
- Translating feedback to the project and thus safeguarding the interests.

BOUWEN VAN H₂ TINY HOUSE

+ WATERSTOF WIJK

+ BEDRIJFSLEVEN

+ ALFA-COLLEGE
ENERGIE EN DUURZAAMHEIDSCENTRUM

= TINY HOUSE



WATERSTOF TINY HOUSE







WATERSTOF

IN HET WATERSTOF TINY HOUSE

remeha

remeha






NAV

fensplanet



WELKOM IN HET WATERSTOF TINY HOUSE



HYBRIDE



Green Deal H2-Wijken





**Hanzehogeschool
Groningen**
University of Applied Sciences

Monitor Waterstofwijk Hoogeveen, eerste peiling informatiebehoefte en draagvlak



Inventarisatie waterstofveiligheid in en om woningen in pilotprojecten

Een uitgave van DNV in opdracht van het Ministerie van Economische Zaken en Klimaat

Rapport nr.: 24-1153, versie 8.0
Datum: 25 juli 2024



Rijksdienst voor Ondernemend
Nederland

Pilotprojecten waterstof in de gebouwde omgeving

Leerervaringen

>> Duurzaam, Agrarisch, Innovatief
en Internationaal ondernemen



Hydrogen testnetwork EnTranCe, Hanze University Groningen

RENDO, Cogas
en BAM Energie
& Water

Test network H2: a learning and safe
environment for practical experience
with hydrogen in the built
environment in the field of safety,
management and maintenance.



Implementation



Partners



Hydrogen network including the H2 meter



Hydrogen discharge station



Hydrogen receiving station

essent

Energy supplier



Hydrogen boilers









Progress

New-build homes Nijstad-Oost: all plots have now been provisionally sold and the plans are now being worked out for building permits.

Preliminary study electrolyser completed, feasibility phase starts soon.

Start lobby together with RENDO for creating a regional hydrogen network that can be connected later with the national hydrogen infrastructure.

Gasunie has modified the system to get the odorization in order, then connection of first home.

Decision-making for up-scaling in municipal council prepared



"Please be patient": How to ensure public support now that the start of the project is being postponed time and again?

First 9 homes:

9 households signed pilot agreement before summer 2024.

Intention was to connect 9 homes in September 2024

Due to odorization challenge, no real homes connected at this time.

The message is; "Please be patient"

Keep up to date.

Problems with current natural gas boiler solved immediately

Energy price April 2024 applies unless price is lower now.



Public Support

For the rest of the neighborhood (427 homes):

- First connect 9 homes and then a resident survey about the plan to become natural gas free neighborhood.
- Then city council decides to scale up to 100 hydrogen connections.
- Plan to become a natural gas free neighborhood (magazine): to make sure there is a perspective for the other 327 homes
- 3 options: hydrogen, hybrid heat pump, all electric
- Free energy advice of the municipality tailored to the specific home and lifestyle, so that residents can make an informed choice.



Odorization is a challenge

- The system must be able to serve one home but also to serve 200 in the end. That in combination with odorization of hydrogen at low flow is a complex task.
- System adjusted: odorant did not mix sufficiently with the hydrogen. Now partial flow of hydrogen is heated so that the odorant evaporates, works well
- New problem during testing: measurement errors due to large temperature differences in the morning and evening
- This month a new odorant system from another manufacturer was installed, with good results.
- Decision at the end of October, planning the conversion of the first 9 homes.





Westfalen

23
1049



MS W 2027



The Hydrogen Chain in Hooftveen

Hydrogen Hooftveen is a pilot project within the national program "Aardgasvrije Wijken". In this project, we are exploring how to heat neighborhoods without using natural gas. We are gathering knowledge and examining what is needed to use hydrogen on a larger scale after 2030. This includes technical solutions, hydrogen boilers, safety, well-trained installers, and clear legislation.

On this page, we show the steps we are taking, who is involved, and what we are learning from this project.



Next steps

Connection of homes tot Hydrogen

- Odorisation in order
- Connecting the first 9 homes
- Resident survey
- Municipal council decision to scale up to 100 homes in existing neighborhood
- Planning for scaling up in Erflanden
- Planning installation of hydrogen boilers in 100 new-build homes

Availability of affordable green hydrogen

- Ensuring with partners that the pilot ammonia cracker is realized
- hydrogen via pyrolysis of biogas from manure
- Feasibility study electrolyser
- Lobby regional hydrogen network and connection to national infrastructure
- Smart Energy Hydrogen Hubs



Contact Details

Kees Boer
Projectmanager Hydrogen District| Municipality of Hoogeveen
The Netherlands
+31 646382093
k.boer@dewoldenhoogeveen.nl



